



5...4...3...2...1...

SPACE LAUNCH SYSTEM

Developing the World's Most
Powerful Solid Rocket Booster

Alex Priskos
May 5, 2016


Space Propulsion Conference




Agenda

- **SLS Overview**
- **Booster Overview**
- **Significant Accomplishments**
- **Challenges**
 - Forward Skirt
 - Abnormal nozzle erosion
 - PLI unbond
- **A Look Ahead**


SLS BLOCK 1 CREW VEHICLE



SLS EVOLUTION




SLS FIVE-SEGMENT BOOSTERS



Significant Accomplishments



EM-1 motor case
hardware refurbishment



Avionic system level testing



EM-1 LH aft skirt refurbishment




QM-2 aft segment
delivery to test stand



QM-1 static test

Challenges – Forward Skirt



◆ Issue

- Predicted SLS loads at the forward thrust post were increased over what was seen during the SSP.



◆ Action Taken

- Two forward skirt structural test articles were tested to failure (liftoff and ascent loads).

◆ Results

- Both tests determined the failure point was beyond required capability.
- Testing and analysis showed that the heritage forward skirt design can be used for SLS, eliminating the need for a redesign.

Challenges – Abnormal Nozzle Erosion



◆ Issue

- DM-2 and DM-3 FNR experienced abnormal erosion at the bottom of the nozzle

◆ Likely causes: TVC duty cycle, slag

- Needed validation by additional testing


◆ Action Taken

- Instrumented DM-3 with ultrasonic gauges, capturing the timing and magnitude of erosion
- TVC duty cycle and slag were not contributors to abnormal erosion; particle impingement and environments found to be the contributors

◆ List of mitigations

- FNR ply angle change
- FNR material change
- Additional mid-span support to reduce sag during static test

Challenges – PLI Unbond



◆ Issue

- PLI unbonds found during x-ray inspection of the QM-1 aft segment

◆ Root cause

- Insulation outgassing during cast/cure

◆ Initial mitigation

- Drive out all gases from the insulator with a VDVC
- Unsuccessful cast of 2nd aft segment


◆ Follow-on investigation

- Additional subscale and substantial full-scale testing
- Dissection of 2nd aft segment unbond
- Validated original root cause

◆ Follow-on mitigation


- Improved insulation layup
- Improved vacuum cycle
- Barrier and cap ply design

A Look Ahead at the Home Stretch



- ◆ Currently finishing up qualification efforts
- ◆ Fabrication of EM-1 hardware is underway
- ◆ Preparing for launch site testing and integration

Questions



www.nasa.gov/marshall